Concrete cracks: identify and assess

Appearance alone does not establish the cause or structural significance.

Build Supply | SulfRock | Intelligent Panel Systems | HomePod

1 Early-age cracking

Plastic shrinkage and settlement can occur before hardening. Review placement, evaporation, compaction and curing records.

2 Later-age movement

Drying, temperature changes and restraint can create cracking after hardening.

3 Loading and support

Structural loading or support movement needs engineering assessment. Do not classify solely from crack direction.

4 Corrosion and deterioration

Rust staining, delamination or spalling may indicate reinforcement problems or other deterioration.

5 Record the evidence

Map position, length and width; note change over time, exposure, leakage and associated distortion.

6 Choose a repair after diagnosis

Specify repair for the cause, activity and required performance. There is no single safe crack-width limit for every structure.

Restrict access and seek prompt engineering advice where distress, instability or falling concrete is suspected.

REFERENCE GUIDANCE

ACI: causes and evaluation of concrete cracking
Concrete Society: repair selection

Use current product instructions and the approved project design. For regulations, confirm the UK nation, applicable edition and transitional arrangements.

Help us keep our information accurate.

If you notice an error, outdated information or something that needs clarification in this document, please let us know.
Report an Issue: Visit our website and select Report a Website or Document Issue.
homepodltd.com